

## MUMBAI METRO RAIL CORPORATION LTD (MMRC)

MMRC, 1<sup>st</sup> Floor, MMRC Transit office, Plot No. R-13, E-Block, Bandra Kurla Complex,  
Bandra (East), Mumbai - 400 051

No.MMRC/ML-3/Car Depot/Grouting/23

Date : 05/12/2023


### SHORT QUOTATION NOTICE

The Deputy General Manager, Car Depot, MMRC invites sealed quotation on the letter head for the work mentioned below from the registered contractors who have carried out similar type of work.

1. **Name of Work** : Grouting the gap between column pedestal and steel column base plate with Non-shrink high strength grout at stabling yard-2 & station PEB structure at Aarey colony car depot project
2. **Issue of Blank Quotation Form (Schedule - B)** : From 05/12/2023 to 12/12/2023 during office hours 11.00 hrs. to 15.00 hrs.
3. **Date of receipt of sealed Quotation** : 13/12/2023 upto 15.00 hrs. at above mentioned Address.
4. **Time and Date of opening of sealed quotations.** : 13/12/2023 after 15.00 hrs, if possible.
5. **Time limit for completion** : 10 days

Note :1) Before submitting quotations, the contractors are requested to inspect the site conditions.

- 2) The lowest quotation received will have to make necessary agreement.
- 3) The sealed quotation should reach this office on or before 13/12/2023 upto 15.00 hrs.
- 4) The above quotation rates will be valid for Six months.
- 5) The contractor has to complete the works as early as possible as per the direction of Engineer-in-charge.
- 6) Blank quotation form (Schedule - B) is attached. For any additional information please contact Shri. S.D.Aher (Deputy Engineer) on cell no. 8446127988.

  
(R.A.Patil)  
05/12/2023  
Deputy General Manager

**Copy to :** Notice Board of MMRC.  
**Encl:** Schedule-B

**SCHEDULE - B (BILL OF QUANTITIES)**

Name of Work : Grouting the gap between column pedestal and steel column base plate with Non-shrink high strength grout at stabling yard-2 & station PEB structure at Aarey colony car depot project

Item No	Items	Unit	Qty.	Rate (Rs.) (Exclusive of GST)		Amount (Rs.)
				In Figures	In Words	
1	2	3	4	5	6	7
1	Grouting the gap between column pedestal and steel column base plate with ready to use non-shrink high strength grout of approved make as per manufacturers specifications including roughening of surfaces, cleaning with air/water jets with curing.	Kg	10500	135.00	One hundred thirty five only	1417500.00
	<b>Total (Rs)</b>					
	<b>Say (Rs)</b>					

**Grand Total :- Fourteen lakh seventeen thousand five hundred only (Excluding GST)**

I / We agree to carry out the above work @ \_\_\_\_\_ % below/above the estimated rates.

  
(SIGNED)